



NOTES:

1. IF SEWER LATERAL IS DAMAGED OR HAS TO BE RELOCATED DURING CONSTRUCTION, RELOCATE/REPAIR SEWER PIPE AND RECONNECT USING A FERNCO RC SERIES STRONGBACK COUPLING OR ROMAC COUPLING.
2. INSPECTION OF WORK IS REQUIRED AND MUST BE APPROVED BY THE ENGINEERING DEPARTMENT.
3. BORING OF SERVICES WITHIN RIGHT OF WAY IS NOT ALLOWED.
4. SEWER PIPE SHALL BE SDR-35 AND JOINTS SHALL BE GASKETED.



CITY OF EDMONDS
PUBLIC WORKS
DEPARTMENT

SIDE SEWER RELOCATION/REPAIR

APPROVED BY: R. ENGLISH

REVISION DATE
FEBRUARY 2023

STANDARD
DETAIL
SS-201